

2017 Street Improvement Project

Asphalt Paving

- 1) Liberty Road – South Street to Lower Bloomfield
 - 3006' x 20'
 - 60,120 square feet
 - 2" thickness
 - 724 tons

(***Milling will need to be done along much of Liberty Road. It is the contractor's responsibility to communicate with the Village Operations Manager, Matt Wood, to coordinate where milling needs to occur **PRIOR** to submitting bids. Matt may be reached at 740-826-7671)

- 2) Stag Alley – westernmost section at intersection of Montgomery Blvd
 - 170' x 14'
 - 2,380 square feet
 - 1.5" thickness
 - 22 tons

- 3) Sunafrank Alley from Cherry Lane to High St
 - 175' x 18'
 - 3,150 square feet
 - 2" thickness
 - 38 tons

- 4) Chestnut St north of Main St
 - 185' x 12'
 - 2,220 square feet
 - 1.5" thickness
 - 21 tons

- 5) Lakeside Drive – South of SRTS Project end
 - 212' x 18'
 - 3,816 square feet
 - 1.5" thickness
 - 35 tons

Total Paving cost estimate: \$86,000

Concrete Streets

Harper Avenue – Replacing a 10' x 12' section at 6" thickness

Total Concrete Street Cost Estimate: \$2,000